

ARNHEM, Neatherlands

Bridge Protection Insulation for Trolleybus

Client: Connexion Trolleybus Arnhem, Westervoordsedijk 4, 6827 AS Arnhem

Contractor: Connexion Trolleybus Arnhem, Westervoordsedijk 4, 6827 AS Arnhem

Construction Manager: Hans Aldenkamp, Phn: +31 26 357 4xxxx, GSM:+31 6 18501xxx

Contract Amount: 25.000 €

Construction/Delivery Period: April - June 2020

Project Description:

After the accident involving the old bridge protection, a new bridge protection system was planned, manufactured, and delivered following detailed planning. Bridge protection insulation designed as a trough; 2 FR, 25m x 1m wide.

Main Services / Deliveries:

- Planning of bridge protection insulation
- Steel substructure
- Use of the innovative Ivema bridge clamp
- GRP H-profiles and side trough guide
- Sandwich panels



Ivema-Fahrleitungsbau GmbH
Dessauerstr. 60
45472 Mülheim an der Ruhr
Germany

Copyright © Ivema 2020. (Urheberschutzrechte sind zwingend zu beachten)