

BREMEN, Germany

BSAG, Overhead Conductor Rails in the Hall

Client: Bremer Straßenbahn AG, Flughafendamm 12, 28199 Bremen

Contractor: Bremer Straßenbahn AG, Flughafendamm 12, 28199 Bremen

Construction Manager: Frank Martsch, Phn: +49 421 5596-xxxx

Contract Amount: 49.000 €

Construction/Delivery Period: November 2019 - March 2020

Project Description:

Ceiling conductor rail equipment in the tram maintenance halls: 3x45m in the main depot at Flughafendamm and 2x30m in the Sebaldsbrück depot, with a high elevation in the entrance gate area.

Main Services / Deliveries:

- Planning
- Aluminum ceiling conductor rails
- Holders / suspension insulators
- Steel crossbeams / brackets
- Ramps



Ivema-Fahrleitungsbau GmbH
Dessauerstr. 60
45472 Mülheim an der Ruhr
Germany

Copyright © Ivema 2020. (Urheberschutzrechte sind zwingend zu beachten)